




EN: This Datasheet/Document is presented by the manufacturer.

Please visit our website for pricing and availability at www.hestore.hu.

Dept
Qty
DC 1
ED 1
IE 1
ISO 1
PD 1
R&D 1
SD 1
QA 1
QC 1
QE 1

The information provided herein is from CONNELY Electronic Co., Ltd. and is confidential. Any disclosure to a party other than the recipient is prohibited. The intellectual properties and its rights contained herein, including but not limited to, trademarks, patents, copyrights, trade secrets, and technical know-how, are owned exclusively by CONNELY or its affiliates. Unauthorized use of this information for any purpose other than the intended use is prohibited. CONNELY may enforce its intellectual property rights at its own discretion, failures or delays to exercise such rights does not constitute a waiver of such rights.

REV.	DESCRIPTION	DRAWN	CHECKED	APPROVED
A	NEW RELEASE	YCH 08/18/07		LJC 08/18/07
D	DRAWING UPDATE	JLZ 05/22/19'		



- NOTES:
- Insulation material: PVC
Color: Grey or dark grey
 - Specification
Rating: 300V
Conductor Size: 28~30AWG
Insulation resistance: 100MΩ/km min.
Operating temperature:-20°C~70°C.
 - Application
Internal wiring of computers,electronic exchanges,measurement control devices, business machines,communication devices, and other electronic equipment.

4. Product Number Code
DS1057-01 - X X X X X - X

Packing Specifications
30.5: 30.5M/reel
60.1: 60.1M/reel
76.5: 76.5M/reel
153.0: 153M/reel


Edge mark
R:Red mark
F:Flower mark

Wire diameter
1: Ø0.100 (30AWG)
2: Ø0.127 (28AWG)


Wire AWG
28: 28AWG
30: 30AWG

Cable color
A: Gray
S: Dark grey

No.Of positions
06: 6 Pin
.....
64: 64 Pin



Number	Dimensions			Max. conductor resistance DC 20°C Ω/m
	TP(mm)	W(mm)	Tolerance	
06	5.00	6.00	±0.30	Ø0.100<0.397 Ø0.127<0.237
08	7.00	8.00	±0.30	
10	9.00	10.00	±0.30	
14	13.00	14.00	±0.30	
16	15.00	16.00	±0.30	
20	19.00	20.00	±0.30	
24	23.00	24.00	±0.30	
26	25.00	26.00	±0.30	
30	29.00	30.00	±0.30	
34	33.00	34.00	±0.40	
40	39.00	40.00	±0.40	
50	49.00	50.00	±0.40	
60	59.00	60.00	±0.40	
64	63.00	64.00	±0.40	



GENERAL TOLERANCE		ANGLE TOLERANCE		PROJECTION	TITLE	UL 2651 PITCH 1.00mm FLAT CABLE	
X.	±0.60	X.	±5°	UNITS	mm		
.X	±0.38	.X	±3°	SHEET SIZE	A4	SERIES	DS1057-01 SERIES
.XX	±0.25	.XX	±2°				
DRAWING TYPE	CUSTOMER						
SCALE	1:1	SHEET	1 OF 1				
DRAWING NO.	C-DS1057-01-XXXXX-X-D						



晨翔电子有限公司
CONNELY ELECTRONIC CO. LTD